BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/10/2019-20 Dated: 04-10-2019

APPROVED TENDER SCHEDULE –'B'

Item-12

Name of Work:-Emergency works in ward No-04 yelahanka division.

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri G V HEMANTHRAJA (SRI LAKSHMI VENKATESHWARA ENTERPRISES)	
				Rate	Rate in Words
1	Supplying and fixing precast rainforced concrete slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials. (Drain covering slab)	sqm	49.50	2098.86	Rupees Two Thousand Ninety Eight and Paise Eighty Six Only
2	Providing precast slab of 250 mm thick including cost of all materials, labour, curing, transportation, loading ,unloading,etc.,complete as per the direction of engineer in charge-	sqm	7.00	4865.91	Rupees Four Thousand Eight Hundred Sixty Five and Paise Ninety One Only
3	Engaging on Hire Basis JCB including Driver/operator with fuel etc complete (SR 2018-19) Page No XLVIII code 1031)	Day	2.00	5114.68	Rupees Five Thousand One Hundred Fourteen and Paise Sixty Eight Only
4	Engaging on Hire basis of Tractor 50 HP for Conveying of excavated and removal of Stuff from work spot (SR 2018-19) Page No XLVIII code 1024)	Day	75.00	1912.05	Rupees One Thousand Nine Hundred Twelve and Paise Five Only
5	Labour charges to Unskilled Mazdoor Heavy (Page no .LVI)SR 2018-19 sl No 5	Day	450.00	400.73	Rupees Four Hundred and Paise Seventy Three Only
6	Providing and fixing pre cast solid concrete kerb stones of size 450x150x500 mm made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting ete., complete.Page No. 27/ Item No. 5.29.2/ PWD SR 2018-19	Nos	111.11	427.75	Rupees Four Hundred Twenty Seven and Paise Seventy Five Only
7	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in Ordinary soil not exceeding 1.5 m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications (P.NO - 6, I.NO - 2.3, PWD SR 18-19)	Cum	180.00	284.64	Rupees Two Hundred Eighty Four and Paise Sixty Four Only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri G V HEMANTHRAJA (SRI LAKSHMI VENKATESHWARA ENTERPRISES)	
				Rate	Rate in Words
8	Providing and installing at site of work 63mm (0.662) PVC Pipes of 6 kg / cm2 including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe alround to a depth not less than 15cms with gravel or selected earth available from the excavation etc., complete (P.NO - 94, I.NO - 13.73.2, PWD SR 18-19)	Mtr	400.00	354.14	Rupees Three Hundred Fifty Four and Paise Fourteen Only
9	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specifications (P.NO - 7, I.NO - 2.11, PWD SR 18-19)	Cum	120.00	115.19	Rupees One Hundred Fifteen and Paise Nineteen Only
10	KSRB 14.6-1 : Providing and laying heavy duty cobble stones 60mm thick interlock pavers, using cement and course sand for manufactures of blocks of approved size , shape and colour with a minimum compressive strength of 281kgs per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour, curing complete as per specifications. Page No.103/ Item No. 14.6 / PWD SR 2018-19	sqm	74.00	1002.44	Rupees One Thousand Two and Paise Forty Four Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.